

North Airfield Drainage Improvements O'Hare Airport

to the Core.
Integrity



North Airfield Drainage
Improvements Project Willow
Higgins Reservoir, O'Hare Airport,
Chicago, Illinois

Contract Value: \$38,800.00

Start Date:
September 2003

End Date:
September 2003

Project Reference:
Griffin DeWatering Midwest, LLC
Harry Bagherzadeh
(803) 217-5123

Miller supplied air rotary drilling techniques and support crews to drill using 10-inch casing advance technologies and install ten (10) 6-inch wells to 35-feet below ground surface with 15-feet of 0.020-inch slotted PVC screen and riser to 2.5-feet above ground surface.

Casing was advanced to top of bedrock, approximately 20-feet below ground surface. After bedrock penetrated, we drilled through the 10-inch casing utilizing 9-inch air rotary drilling methods to 35-feet below ground surface. All wells were converted to 6-inch PVC wells.



M MILLER
DRILLING COMPANY

Certified by the Small Business Administration as a HUBZone Business

107 Helton Drive | Lawrenceburg, Tennessee 38464
(931) 762-7548

sales@millerdrilling.com
www.millerdrilling.com